

GENERAL SUMMARY

Prepared for: Salato Pompano Beach 305 Briny Avenue, FL 33062
Project ID: 30052024
Scope: Concrete
No. Of Floors: 9
Date: 30-May-24



BUILDING GSF		174,692	
SITE GSF		58,100	
DIVISION NO	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	General Requirements	\$ 720,000	\$ 4.12
3000	Concrete	\$ 8,083,568	\$ 46.27
32000	Site Improvements	\$ 313,691	\$ 5.40
TOTAL TRADE COST		\$ 9,117,259	\$ 55.79
OVERHEAD AND PROFIT		10%	\$ 911,726
INSURANCE		3%	\$ 273,518
CONTINGENCY		5%	\$ 455,863
TAX		7%	\$ 343,580
SUGGESTED BID		\$ 11,101,945	\$ 70



DETAILED BREAKDOWN OF ITEMS

Prepared for: Salato Pompano Beach 305 Briny Avenue, FL 33062
 Project ID: 30052024
 Scope: Concrete



Date: 7-May-24

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTIT Y	WASTAG E	QUANTITY W/WASTAGE	UNTT MANHOU R	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
948			P7-Precast Concrete Pavers Size: 12" x 12" x 2-3/8" Color: White	SF	222	5%	233	0.075	\$ 30.00	\$ 2.25	\$ 4.62	\$ 6.87	\$ 1,602
949			P8-Precast Concrete Pavers Size: 8" x 8", 8" x 12", 12" x 12", 16" x 16" By 2-3/8" Thk Color: White	SF	6439	5%	6761	0.075	\$ 30.00	\$ 2.25	\$ 4.62	\$ 6.87	\$ 46,457
950			1" Polymer Modified Mortar	CY	20	5%	22	1.650	\$ 30.00	\$ 49.50	\$ 165.00	\$ 214.50	\$ 4,612
951			Waterproofing (By Others)	SF	6661	5%	6994	0.010	\$ 30.00	\$ 0.30	\$ -	\$ 0.30	\$ 2,098
952			1" D Sand Setting Bed @ Pavers	SF	6232	5%	6544	0.003	\$ 30.00	\$ 0.09	\$ 1.97	\$ 2.06	\$ 13,484
953			Mirafi 140N Geotextile	SF	6232	5%	6544	0.010	\$ 30.00	\$ 0.30	\$ 0.27	\$ 0.57	\$ 3,737
954			8" Thk Limerock Aggregate Base	CY	155	5%	162	0.008	\$ 30.00	\$ 0.24	\$ 0.98	\$ 1.22	\$ 198
955			12" Thk Compacted Subgrade	CY	231	5%	242	0.010	\$ 30.00	\$ 0.30	\$ 1.31	\$ 1.61	\$ 390
956			1-1" Thk x 2'-4" H Concrete Planter Wall	CY	5	5%	5	3.000	\$ 30.00	\$ 90.00	\$ 240.00	\$ 330.00	\$ 1,717
957			Formwork	SF	247	5%	259	0.092	\$ 30.00	\$ 2.76	\$ -	\$ 2.76	\$ 716
958			8" Thk x 2'-4" H Concrete Planter Wall	CY	3	5%	3	3.000	\$ 30.00	\$ 90.00	\$ 240.00	\$ 330.00	\$ 902
959			Formwork	SF	210	5%	220	0.092	\$ 30.00	\$ 2.76	\$ -	\$ 2.76	\$ 608
960			1'-6" Thk x 2'-4" H Concrete Planter Wall	CY	3	5%	4	3.000	\$ 30.00	\$ 90.00	\$ 240.00	\$ 330.00	\$ 1,211
961			Formwork	SF	126	5%	132	0.092	\$ 30.00	\$ 2.76	\$ -	\$ 2.76	\$ 365
962			Built In Concrete Bench @ Planter	CY	5	5%	5	3.000	\$ 30.00	\$ 90.00	\$ 240.00	\$ 330.00	\$ 1,677
963			Concrete Planter Wall	CY	43	5%	45	3.000	\$ 30.00	\$ 90.00	\$ 240.00	\$ 330.00	\$ 14,801
964			Formwork	SF	3639	5%	3821	0.092	\$ 30.00	\$ 2.76	\$ -	\$ 2.76	\$ 10,547
965			Concrete Planter Double Wall (6" Thk & 4'-2" H)	CY	22	5%	23	3.000	\$ 30.00	\$ 90.00	\$ 240.00	\$ 330.00	\$ 7,701
966			Formwork	SF	2400	5%	2520	0.092	\$ 30.00	\$ 2.76	\$ -	\$ 2.76	\$ 6,956
967			6" x 1'-0" Concrete Curb @ Pavers To Wood Deck Edge	LF	213	5%	224	0.075	\$ 30.00	\$ 2.25	\$ 7.56	\$ 9.81	\$ 2,194
SUBTOTAL												\$ 313,691	

PROJECTED COST		\$9,117,259
OVERHEAD AND PROFIT	10%	\$911,726
INSURANCE	3%	\$273,518
CONTINGENCY	5%	\$455,863
TAX	7%	\$343,580
SUGGESTED BID		\$11,101,945

Notes:

1. Online sources are used for pricing.
2. Prices can vary depending upon field conditions.

DETAILED BREAKDOWN OF ITEMS

Prepared for: Salato Pompano Beach 305 Briny Avenue, FL 33062
 Project ID: 29052024
 Scope: CONCRETE



SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE
GENERAL REQUIREMENTS							
1			Permits	LS	1	0%	1
2			Supervision and Coordination	LS	1	0%	1
3			Submittals and Shop drawings	LS	1	0%	1
4			Final Cleaning	LS	1	0%	1
5			Mobilization Costs	LS	1	0%	1
6			Temporary Control & Facilities	LS	1	0%	1
7			Scaffolding	LS	1	0%	1
CONCRETE							
CAST IN PLACE CONCRETE							
CONCRETE							
8			3000 Psi Concrete	CY	192	10%	211
9			4000 Psi Concrete	CY	739	10%	813
10			5000 Psi Concrete	CY	2563	10%	2819
11			6000 Psi Concrete	CY	6831	10%	7514
12			8000 Psi Concrete	CY	1164	10%	1280
REINFORCEMENT BARS							
13			#3 Rebar (20' L)	EA	13525	10%	14878
14			#4 Rebar (20' L)	EA	3647	10%	4012
15			#5 Rebar (20' L)	EA	15921	10%	17513
16			#6 Rebar (20' L)	EA	8788	10%	9667
17			#7 Rebar (20' L)	EA	374	10%	412
18			#8 Rebar (20' L)	EA	1850	10%	2035
19			#9 Rebar (20' L)	EA	500	10%	550
20			#10 Rebar (20' L)	EA	774	10%	851
21			#11 Rebar (20' L)	EA	68232	10%	75055
STUD RAILS							
22			(1/2") Dia Stud @ Rail	EA	10099	0%	10099
POST TENSIONING REBAR							
23			1/2" Dia Post Tensioning Rebar (200' L)	EA	182	10%	200
EXCAVATION & BACKFILL							
24			Excavation	CY	6928	10%	7621
25			Backfill	CY	944	10%	1038
FORMWORK							
26			Formwork	SF	454579	10%	500037
MISC							
27			12" D Cont. Key	LF	87	10%	96
28			15 Mil Vapor Retarder	SF	30887	10%	33976
29			Water proofing Membrane	SF	5351	10%	5886
30			6" Granular Fill	CY	565	10%	622
31			Clean Granular Compacted Fill	CY	5203	10%	5723
32			Compacted Subgrade	SF	30512	10%	33563
33			Permeable Compacted Subgrade	SF	268	10%	295
34			12" Thk Compacted Subgrade	SF	231	10%	254
SITE IMPROVEMENT							
SITE CONCRETE							
35			Concrete Sidewalk	SF	2526	10%	2779
36			1/2" Premolded Expansion Joint @ 60' O.C	LF	42	10%	46
37			1/8" x 1-1/2" Construction Joint @ 5' O.C	LF	505	10%	556
38			1/8" x 1/2" Construction Joint @ 20' O.C	LF	126	10%	139
39			6" W x 1'-0" H Concrete Curb & Gutter	LF	226	10%	249
40			6" W x 1'-6" H Concrete Curb	LF	253	10%	278
41			6" Thk Concrete Dumpster Apron	SF	220	10%	242
42			Concrete ADA Entry Ramp	SF	213	10%	234
43			Railing Posts Footing @ Entry Ramp	CY	0.4	10%	0
44			1'-6" W x 12" D Concrete Header Band	LF	253	10%	278
45			P1-Precast Concrete Pavers Size: 4" x 8" x 2-3/8" Color: Charcoal	SF	4378	10%	4816

DETAILED BREAKDOWN OF ITEMS

Prepared for: Salato Pompano Beach 305 Briny Avenue, FL 33062
 Project ID: 29052024
 Scope: CONCRETE



SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE
46			P2-Precast Concrete Pavers Size: 4" x 16" x 2-3/8" Color: Charcoal	SF	1507	10%	1658
47			P3-Precast Concrete Pavers Size: 4" x 8" x 2-3/8" Color: Charcoal AND P4-Precast Concrete Pavers Size: 4" x 8" x 2-3/8" Color: Natural Grey	SF	347	10%	382
48			P5-Precast Concrete Pavers Size: 12" x 12" x 2-3/8" Color: Charcoal	SF	268	10%	295
49			1.5" Thk Drainage Aggregate (Type No. 8)	CY	1	10%	1
50			6" Thk Permeable Base (Type No.57 Aggregate)	CY	5	10%	5
51			6" Thk Permeable Base (Type No.2 Aggregate)	CY	5	10%	5
52			Permeable Compacted Subgrade	SF	268	10%	295
53			P7-Precast Concrete Pavers Size: 12" x 12" x 2-3/8" Color: White	SF	222	10%	244
54			P8-Precast Concrete Pavers Size: 8" x 8", 8" x 12", 12" x 12", 16" x 16" By 2-3/8" Thk Color: White	SF	6439	10%	7083
55			1" Polymer Modified Mortar	CY	20	10%	23
56			Waterproofing (By Others)	SF	6661	10%	7327
57			1" D Sand Setting Bed @ Pavers	SF	6232	10%	6855
58			Mirafi 140N Geotextile	SF	6232	10%	6855
59			8" Thk Limerock Aggregate Base	CY	155	10%	170
60			12" Thk Compacted Subgrade	SF	6232	10%	6855
61			6" x 1'-0" Concrete Curb @ Pavers To Wood Deck Edge	LF	213	10%	234
62			CONCRETE Concrete	CY	142	10%	156
63			REINFORCEMENT BARS @ SITE #4 Rebar (20' L)	EA	30	10%	33
64			#5 Rebar (20' L)	EA	113	10%	124
65			EXCAVATION & BACKFILL Excavation	CY	146	10%	161
66			Backfill	CY	91	10%	100
67			FORMWORK Formwork	SF	9667	10%	10634

PROJECTED COST

OVERHEAD AND PROFIT

INSURANCE

CONTINGENCY

TAX

UGGESTED BID

Notes:

sources are used for pricing.
 ry depending upon field conditions.